



**HUNT MIDWEST REAL ESTATE DEVELOPMENT, INC.
1881 MAIN STREET, SUITE 200
KANSAS CITY, MISSOURI 64108**

**KCI 29 Logistics Park
Public Street Improvement Package**

**BID ADDENDUM #2
6-9-2023**

The following modification have been made to the Bid Documents:

Bid Documents

- Plans
 - Sheet 6:
 - Portland Cement Concrete Pavement (8") = 17,263 SY
 - Portland Cement Concrete Pavement (12") = 6,781 SY
 - Quantity for Concrete Slope Drains has been updated
 - Sheets 13-15: Pavement sections have been modified
 - Sheet 37: Flumes at Stations 241+49 and 242+52 will be paid as Concrete Gutter Type A on the Bid Form
 - Sheets 44-48:
 - Sheets 44-46 are deleted.
 - All concrete pavement jointing shall conform with MoDOT Standard Details as shown on sheets 47 and 48
 - Interface between concrete pavement and concrete curb shall be a longitudinal joint similar to detail L1 on Sheet 47.
 - Sheet 62: Aggregate depth below concrete surface drains shall be 8"
 - Sheets 103-111:
 - These sheets have been deleted and replaced with Sheets A2.1 through A2.9
 - A table of pay items has been included on Sheet A2.1
 - This table should be used only to identify materials and equipment necessary to perform the Work. It should not be considered exhaustive.
 - Street Lighting and Traffic Signal will still be bid as lump sums per the Bid Form, and the Successful Bidder will be responsible to furnish and install all material necessary to complete the Work without regard to the material's presence in or absence from the table on Sheet A2.1
- Bid Form
 - Pavement quantities have been updated
 - Concrete Slope Drain quantity has been updated
- Updated CAD file has been included in the Online Plan Directory

Updated Bid Documents can be obtained at the link below or by contacting the Project Representative at ayoung@huntmidwest.com.

Online Plan Drive: <https://drive.google.com/drive/folders/1LFMfeuaGEEh1nijtS-VgmwH5LK88enct?usp=sharing>

END ADDENDUM #2